

铜仁市石阡县白沙镇2019年度高标准农田建设项目工程量清单

序号	工程或费用名称	单位	数量	单价(元)	合计(元)	备注
第一部分 建筑工程						
(一)	水利工程					
I	大堰村项目区	亩	340.00			
1	灌溉渠道工程	Km	1.15			
1.1	1#灌溉渠道工程	Km	1.15			
(1)	沟槽土方开挖	m ³	437.00			
(2)	沟槽石方开挖	m ³	23.00			
(3)	回填夯实土方	m ³	64.40			
(4)	M7.5浆砌石挡土墙	m ³	11.50			
(5)	C15砼（明渠）	m ³	175.09			
(6)	碎石垫层	m ³	63.25			
(7)	DN110PVC塑料管	m	28.75			
(8)	伸缩缝（聚乙烯板）	m ²	5.75			
(9)	普通平面木模板制作	m ²	1035.00			
(10)	普通平面木模板安装、拆除	m ²	1035.00			
2	田间斗渠工程	Km	0.50			
(1)	沟槽土方开挖	m ³	190.00			
(2)	沟槽石方开挖	m ³	10.00			
(3)	回填夯实土方	m ³	28.00			
(4)	M7.5浆砌石挡土墙	m ³	5.00			
(5)	C15砼（明渠）	m ³	76.13			
(6)	碎石垫层	m ³	27.50			
(7)	DN110PVC塑料管	m	12.50			
(8)	伸缩缝（聚乙烯板）	m ²	2.50			
(9)	普通平面木模板制作	m ²	450.00			
(10)	普通平面木模板安装、拆除	m ²	450.00			
II	花泥田村项目区	亩	700.00			
1	灌溉渠道工程	Km	3.68			
1.1	1#灌溉渠道工程	Km	2.10			
A	拦水堰工程	m	25.00			
(1)	沟槽土方开挖	m ³	125.00			
(2)	沟槽石方开挖	m ³	12.50			
(3)	回填夯实土方	m ³	5.00			
(4)	M7.5浆砌石挡土墙	m ³	106.00			
(5)	C15混凝土基础	m ³	1.70			
B	1#灌溉渠道工程	Km	2.10			
(1)	沟槽土方开挖	m ³	798.00			
(2)	沟槽石方开挖	m ³	42.00			
(3)	回填夯实土方	m ³	117.60			
(4)	M7.5浆砌石挡土墙	m ³	21.00			
(5)	C15砼（明渠）	m ³	319.73			
(6)	碎石垫层	m ³	115.50			
(7)	DN110PVC塑料管	m	52.50			
(8)	伸缩缝（聚乙烯板）	m ²	10.50			
(9)	普通平面木模板制作	m ²	1890.00			
(10)	普通平面木模板安装、拆除	m ²	1890.00			
1.2	2#灌溉渠道工程	Km	1.58			

(1)	沟槽土方开挖	m ³	600.40			
(2)	沟槽石方开挖	m ³	31.60			
(3)	回填夯实土方	m ³	88.48			
(4)	M7.5浆砌石挡土墙	m ³	15.80			
(5)	C15砼（明渠）	m ³	240.56			
(6)	碎石垫层	m ³	86.90			
(7)	DN110PVC塑料管	m	39.50			
(8)	伸缩缝（聚乙烯板）	m ²	7.90			
(9)	普通平面木模板制作	m ²	1422.00			
(10)	普通平面木模板安装、拆除	m ²	1422.00			
2	田间斗渠工程	Km	1.00			
(1)	沟槽土方开挖	m ³	380.00			
(2)	沟槽石方开挖	m ³	20.00			
(3)	回填夯实土方	m ³	56.00			
(4)	M7.5浆砌石挡土墙	m ³	10.00			
(5)	C15砼（明渠）	m ³	152.25			
(6)	碎石垫层	m ³	55.00			
(7)	DN110PVC塑料管	m	25.00			
(8)	伸缩缝（聚乙烯板）	m ²	5.00			
(9)	普通平面木模板制作	m ²	900.00			
(10)	普通平面木模板安装、拆除	m ²	900.00			
III	化塘村项目区	亩	600.00			
1	排水沟工程	Km	0.80			
1.1	1#排水沟工程	Km	0.80			
(1)	土方开挖	m ³	4000.00			
(2)	石方开挖	m ³	150.00			
(3)	回填夯实土方	m ³	200.00			
(4)	M7.5浆砌石挡土墙	m ³	2160.00			
(5)	C15砼压顶	m ³	80.00			
2	田间斗渠工程	Km	0.50			
(1)	沟槽土方开挖	m ³	190.00			
(2)	沟槽石方开挖	m ³	10.00			
(3)	回填夯实土方	m ³	28.00			
(4)	M7.5浆砌石挡土墙	m ³	5.00			
(5)	C15砼（明渠）	m ³	76.13			
(6)	碎石垫层	m ³	27.50			
(7)	DN110PVC塑料管	m	12.50			
(8)	伸缩缝（聚乙烯板）	m ²	2.50			
(9)	普通平面木模板制作	m ²	450.00			
(10)	普通平面木模板安装、拆除	m ²	450.00			
IV	均坪村项目区	亩	820.00			
1	田间斗渠工程	Km	2.70			
(1)	沟槽土方开挖	m ³	1026.00			
(2)	沟槽石方开挖	m ³	54.00			
(3)	回填夯实土方	m ³	151.20			
(4)	M7.5浆砌石挡土墙	m ³	27.00			
(5)	C15砼（明渠）	m ³	411.08			
(6)	碎石垫层	m ³	148.50			
(7)	DN110PVC塑料管	m	67.50			
(8)	伸缩缝（聚乙烯板）	m ²	13.50			

(9)	普通平面木模板制作	m ²	2430.00			
(10)	普通平面木模板安装、拆除	m ²	2430.00			
V	小岩村项目区	亩	500.00			
1	排水沟工程	Km	1.82			
1.1	1#排水沟工程	Km	0.92			
(1)	土方开挖	m ³	920.00			
(2)	石方开挖	m ³	11.50			
(3)	回填夯实土方	m ³	57.50			
(4)	M7.5浆砌石挡土墙	m ³	1104.00			
(5)	M10水泥砂浆抹(平)面	m ²	920.00			
(6)	C15砼底板	m ³	92.00			
(7)	碎石垫层	m ³	92.00			
1.2	2#排水沟工程	Km	0.90			
(1)	土方开挖	m ³	900.00			
(2)	石方开挖	m ³	11.25			
(3)	回填夯实土方	m ³	56.25			
(4)	M7.5浆砌石挡土墙	m ³	1080.00			
(5)	M10水泥砂浆抹(平)面	m ³	900.00			
(6)	C15砼底板	m ³	90.00			
(7)	碎石垫层	m ³	90.00			
2	田间斗渠工程	Km	0.50			
(1)	沟槽土方开挖	m ³	190.00			
(2)	沟槽石方开挖	m ³	10.00			
(3)	回填夯实土方	m ³	28.00			
(4)	M7.5浆砌石挡土墙	m ³	5.00			
(5)	C15砼(明渠)	m ³	76.13			
(6)	碎石垫层	m ³	27.50			
(7)	DN110PVC塑料管	m	12.50			
(8)	伸缩缝(聚乙烯板)	m ²	2.50			
(9)	普通平面木模板制作	m ²	450.00			
(10)	普通平面木模板安装、拆除	m ²	450.00			
VI	岩上村项目区	亩	1200.00			
1	排水沟工程	Km	1.02			
1.1	1#排水沟工程	Km	1.02			
(1)	土方开挖	m ³	4500.00			
(2)	石方开挖	m ³	200.00			
(3)	回填夯实土方	m ³	300.00			
(4)	M7.5浆砌石挡土墙	m ³	2900.00			
(5)	C15砼压顶	m ³	102.00			
(6)	C25砼	m ³	25.00			
(7)	钢筋制安	t	2.50			
VII	袁家坡村项目区	亩	1000.00			
1	灌溉渠道工程	Km	3.48			
1.1	1#灌溉渠道工程	Km	1.88			
A	拦水堰工程	m	20.00			
(1)	沟槽土方开挖	m ³	100.00			
(2)	沟槽石方开挖	m ³	10.00			
(3)	回填夯实土方	m ³	5.00			
(4)	M7.5浆砌石挡土墙	m ³	85.00			
(5)	C15混凝土基础	m ³	1.50			

B	灌溉渠道工程	Km	1.88			
(1)	沟槽土方开挖	m ³	714.40			
(2)	沟槽石方开挖	m ³	37.60			
(3)	回填夯实土方	m ³	105.28			
(4)	M7.5浆砌石挡土墙	m ³	18.80			
(5)	C15砼（明渠）	m ³	286.23			
(6)	碎石垫层	m ³	103.40			
(7)	DN110PVC塑料管	m	47.00			
(8)	伸缩缝（聚乙烯板）	m ²	9.40			
(9)	普通平面木模板制作	m ²	1692.00			
(10)	普通平面木模板安装、拆除	m ²	1692.00			
1.2	2#灌溉渠道工程	Km	1.60			
A	拦水堰工程	m	20.00			
(1)	沟槽土方开挖	m ³	100.00			
(2)	沟槽石方开挖	m ³	10.00			
(3)	回填夯实土方	m ³	5.00			
(4)	M7.5浆砌石挡土墙	m ³	85.00			
(5)	C15混凝土基础	m ³	1.50			
B	灌溉渠道工程	Km	1.40			
(1)	沟槽土方开挖	m ³	532.00			
(2)	沟槽石方开挖	m ³	28.00			
(3)	回填夯实土方	m ³	78.40			
(4)	M7.5浆砌石挡土墙	m ³	14.00			
(5)	C15砼（明渠）	m ³	213.15			
(6)	碎石垫层	m ³	77.00			
(7)	DN110PVC塑料管	m	35.00			
(8)	伸缩缝（聚乙烯板）	m ²	7.00			
(9)	普通平面木模板制作	m ²	1260.00			
(10)	普通平面木模板安装、拆除	m ²	1260.00			
1.3	3#灌溉渠道工程	Km				
A	拦水堰工程					
(1)	沟槽土方开挖	m ³	0.00			
(2)	沟槽石方开挖	m ³	0.00			
(3)	回填夯实土方	m ³	0.00			
(4)	M7.5浆砌石挡土墙	m ³	0.00			
(5)	C15混凝土基础	m ³	0.00			
B	灌溉渠道工程	Km	0.00			
(1)	沟槽土方开挖	m ³	0.00			
(2)	沟槽石方开挖	m ³	0.00			
(3)	回填夯实土方	m ³	0.00			
(4)	M7.5浆砌石挡土墙	m ³	0.00			
(5)	C15砼（明渠）	m ³	0.00			
(6)	碎石垫层	m ³	0.00			
(7)	DN110PVC塑料管	m	0.00			
(8)	伸缩缝（聚乙烯板）	m ²	0.00			
(9)	普通平面木模板制作	m ²	0.00			
(10)	普通平面木模板安装、拆除	m ²	0.00			
2	田间斗渠工程	Km	0.70			
(1)	沟槽土方开挖	m ³	266.00			
(2)	沟槽石方开挖	m ³	14.00			

(3)	回填夯实土方	m ³	39.20			
(4)	M7.5浆砌石挡土墙	m ³	7.00			
(5)	C15砼（明渠）	m ³	106.58			
(6)	碎石垫层	m ³	38.50			
(7)	DN110PVC塑料管	m	17.50			
(8)	伸缩缝（聚乙烯板）	m ²	3.50			
(9)	普通平面木模板制作	m ²	630.00			
(10)	普通平面木模板安装、拆除	m ²	630.00			
(二)	田间道路工程					
I	大堰村项目区					
1	生产便道工程	Km	1.00			
(1)	土方开挖	m ³	75.00			
(2)	石方开挖	m ³	1.00			
(3)	碎石垫层	m ³	150.00			
(4)	C15混凝土路面	m ³	150.00			
II	花泥田村项目区					
1	生产便道工程	Km	1.57			
(1)	土方开挖	m ³	117.75			
(2)	石方开挖	m ³	1.57			
(3)	碎石垫层	m ³	235.50			
(4)	C15混凝土路面	m ³	235.50			
III	化塘村项目区					
1	生产便道工程	Km	1.90			
(1)	土方开挖	m ³	142.50			
(2)	石方开挖	m ³	1.90			
(3)	碎石垫层	m ³	285.00			
(4)	C15混凝土路面	m ³	285.00			
VI	均坪村项目区					
1	生产便道工程	Km	3.26			
(1)	土方开挖	m ³	244.50			
(2)	石方开挖	m ³	3.26			
(3)	碎石垫层	m ³	489.00			
(4)	C15混凝土路面	m ³	489.00			
V	小岩村项目区					
1	生产便道工程	Km	0.79			
(1)	土方开挖	m ³	59.25			
(2)	石方开挖	m ³	0.79			
(3)	碎石垫层	m ³	118.50			
(4)	C15混凝土路面	m ³	118.50			
VI	岩上村项目区					
1	机耕道工程					
1.1	1#机耕道工程	Km				
(1)	土方开挖	m ³	0.00			
(2)	石方开挖	m ³	0.00			
(3)	大碴垫层	m ³	0.00			
(4)	碎石垫层	m ³	0.00			
(5)	C25混凝土路面	m ²	0.00			
(6)	伸缩缝	m ²	0.00			
(7)	M7.5浆砌块石	m ³	0.00			
(8)	dn200混凝土预制管	m	0.00			
(9)	普通平面木模板制作	m ²	0.00			

(10)	普通平面木模板安装、拆除	m ²	0.00			
1.2	2#机耕道工程	Km				
(1)	土方开挖	m ³	0.00			
(2)	石方开挖	m ³	0.00			
(3)	大碴垫层	m ³	0.00			
(4)	碎石垫层	m ³	0.00			
(5)	C25混凝土路面	m ²	0.00			
(6)	伸缩缝	m ²	0.00			
(7)	M7.5浆砌块石	m ³	0.00			
(8)	dn200混凝土预制管	m	0.00			
(9)	普通平面木模板制作	m ²	0.00			
(10)	普通平面木模板安装、拆除	m ²	0.00			
1	生产便道工程	Km	1.66			
(1)	土方开挖	m ³	124.50			
(2)	石方开挖	m ³	1.66			
(3)	碎石垫层	m ³	249.00			
(4)	C15混凝土路面	m ³	249.00			
VII	袁家坡村项目区					
1	生产便道工程	Km	3.08			
(1)	土方开挖	m ³	231.00			
(2)	石方开挖	m ³	3.08			
(3)	碎石垫层	m ³	462.00			
(4)	C15混凝土路面	m ³	462.00			